

Update Seminar July 25, 2007









WELCOME

Cathy Hudgins

Fairfax County Board, Hunter Mill Chair, Transportation Planning Board









Construction: What, Where, and When

Sam Carnaggio
Project Director
Dulles Corridor Metrorail Project







PROJECT BENEFITS Making a 50 Year Vision...A Reality





Dulles Metrorail Extension At-a-Glance

- 23-mile new Metrorail line branching off the Orange Line after East Falls Church
- 11 new stations
 - 5 in Phase 1
 - 6 in Phase 2
- Seamless integration with current 106-mile system
- Approx. 50% of Tysons' commuters originate from eastern points accessible to existing metrorail







New Travel Option for Northern Virginia Benefits of Making a 50 Year Dream... a Reality

- Provide connectivity and pedestrian friendly access to major employment/retail centers and airport
- Gives commuters more travel options
- Leads the way for transformation of Tysons
 - Utilities to be moved underground
 - Sidewalks added to Route 7
 - Pedestrian walkways across key intersections








A Close Look at Phase 1 Stations






Route Map



A Closer Look at Tysons Corner Stations







Tysons East



entrance

entrance

2 escalators, 2 elevators in South

Elevated

Tysons East Station Draft Design



09.26.2006



Tysons Central 123



Galleria

- On Route 123 at Tysons Boulevard
- Elevated
- 2 station entrances on each side of Route 123
- Pedestrian bridge crossing Route 123
- Bus dropoff/pickup on both sides
- 2 escalators, 2 elevators in station
- 1 escalator, 2 elevators in North entrance
- 1 escalator, 2 elevators in South entrance



A Macerich Company Property



Tysons 123 Station Future Development on Tysons Corner Center Site



Pedestrian
Bridge to Station



Tysons Central 7



 On Route 7 just northwest of Route 123

- Partially Underground
- 2 station entrances (each side of Route 7)
- 2 escalators, 2 elevators in station
- 1 escalator, 2 elevators in both North and South entrances

Marshalls.



Tysons West

Elevated


Route 7

station

entrance

entrance


Kiss & Ride





Wiehle Avenue

- In median of Dulles Airport Access Highway
- Ground Level
- 2 station entrances (both sides of Toll Road)
- Pedestrian bridge crossing toll road and airport access highway
- Bus dropoff/pickup;
 Kiss & Ride (north side)
- Parking for 2,300 cars (north side)
- 2 escalators, 2 elevators in station
- 4 escalators, 3 elevators in North entrance
- 2 escalators, 2 elevators in South entrance







MOVING FORWARD Utility Relocation to Begin this Year

- Anticipated start of work Late Summer/Early Fall 2007
- Working with landowners along Route 7 to provide information about likely property impacts
- Official notifications sent to landowners in June
- Relocating utilities prior to construction reduces risk and saves dollars







Utility Relocation: August/September 2007 - Summer 2008


Route 7

- Start at east end of southern side; continue west
- Business access maintained during work/business hours

Route 123

 Relocations only at station sites


No lane closures during peak rush hours on Route 7 or Route 123



Dulles MOT (Maintenance of Traffic) for Utility Relocation and Project Construction

- No scheduled lane closures during peak rush hours
- Entrances to businesses will remain accessible during work hours throughout construction
- Temporary lane closures will be in evenings/weekends
 - All business/residents will be notified in advance through email, direct mail, outreach meetings and advertisement
- Variable message signs will inform and prepare commuters before entering construction areas
- The Project will follow Fairfax County's noise protocols









Dulles MOT (Maintenance of Traffic) Project Construction

- 1st Year of Construction (Reconfiguring Route 7)
 - During Rush Hour: 3 lanes to remain continuously open on Route 7
 - Service roads to be modified
 - No major reconfiguration of Route 123

2nd Year Through End of Construction

During Rush Hour: 4 lanes to remain continuously open on Route 7




- Service road eliminated
- No major reconfiguration of Route 123

Enhancing Route 7

BEFORE



AFTER



NEXT STOP, TYSONS

Dulles Metrorail is on Track!

- Recent Approval of Operation and Financial Agreement by:
 - Fairfax County June 18
 - Loudoun County June 19
 - WMATA Board June 28
- Early July 2007 MWAA & Dulles Transit Partners Sign
 Phase 1 Contract
- Late Summer/Early Fall 2007 Utility Relocation to Start
- 2008 Anticipated FFGA
- 2008 Project Construction Starts

Contact Information



www.dullesmetro.com

703-288-7000

1595 Spring Hill Road, Suite 600 Vienna, VA 22182



